BUILDINGS DIVISION, BANGALORE.

Abstract Notification dated 1st April 1935.

The attention of the public is invited to the notification calling for tenders for constructing a building for locating Arrack and Toddy shops near Binny Mills, Bangalore City, published on pages 768-769 of Part VI of the *Mysore Gazette*, dated 4th April 1935.

The last date of receiving tenders is 27th April 1935.

Abstract Notification dated 1st April 1935.

The attention of the public is invited to the notification calling for tenders for constructing a building for the Boy Scouts' Headquarters Office, Bangalore, published on pages 769-770 of Part VI of the *Mysore Gazette*, dated 4th April 1935.

The last date of receiving tenders is 27th April 1935.

Abstract Notification dated 8th April 1935.

The attention of the public is invited to the Notification calling for tenders for constructing a building for the Testing Laboratory in the Government Porcelain Factory at Bangalore, published on pages 832-834 of Part VI of the *Mysore Gazette* dated 11th April 1935.

The last date of receiving tenders is 29th April 1935.

A. TANDONI RAO,
Executive Engineer.

KOLAR DIVISION.

Notification dated 6th April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 25th April 1935, for Restoring Kongathimmanahalli Thirumalkere Minor Tank, Register No. 417/566 of Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 275 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Kongathimmanahally Tirumalkere Minor Tank, Register No. 417/566 Chintamani Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Kolar, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries, regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. The rates are to be entered both in figures and words.

10. Rates once tendered will on no account be increased afterwards.

11. Tenders stating that the dues in the Department may be adjusted towards earnest money will be rejected.

12. A progress of Rs. 1,000 should be shown every month.

Abstract estimate for restoring Kongathimmanahalli Tirumalkere Register No. 417—566 in Chintamani Taluk.

No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	Bund R. L. 56.00 top width 4½′ slopes 1½ : 1 and 2 : 1.				
1	Jungle clearing and removing ant hills and filling them with sand	Grade	..	26	
2	Removing top soil and cutting trenches and grips	,,	..	26	
3	Earthwork with consolidation	C.yds.	..	6,714	
4	Turfing the slopes of bund	S.yds.	..	6,233	
5	Rough stone work new	C.yds.	..	963	
6	Providing and fixing grade stones including figuring, painting, etc.	Each	..	26	
	Do Index stones	,,	..	26	
7	Do B. M. Stones	,,	..	2	
8	Do Register No. and date stone ..	,,	..	1	
9	Do Gauge stone	,,	..	1	
10	Removing and resetting old stone revetment here and there	C.yds.	..	100	
11	Total for Bund ..				
	Constructing waste weir 290′ Length at R. L. 51·00.				
1	Earthwork excavation in hard Chettu soil ..	C.yds.	..	175	
2	Concrete stone jelly in surki mortar ..	C.ft.	..	700	
3	Burnt brick in surki mortar	,,	..	612	
4	Burnt stone slabs 6″ thick neatly dressed ..	S.ft.	..	904	
5	Plastering with surki mortar	Sqr.	..	11·00	
6	Jaggle joints	Each	..	37	
7	Rough stone work new	C.yds.	..	108	
8	Draft and approach clearing	,,	..	366	
9	Removing boulders here and there	,,	..	10	
	Total for waste weir	..	..	..	
III.	*Repairing the sluice No. I after cutting open the bund and refilling.*	L. S.			
IV.	*Do do No. II* ..	L. S.			
	Grand Total Rs. ..	..	..	..	

N. SUBBA RAO,
Executive Engineer.

TUMKUR DIVISION.

Notification dated 8th April 1935.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. on 25th April 1935 for constructing Middle School at Basappanapalya, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Middle School at Basappanapalya, Tumkur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing a Middle School at Basappanapalya on the existing foundation, Tumkur Taluk.

Sl. No.	Items of work	Per	Quantity	Rate	Cost
				Rs. a. p.	
1	Basement, burnt stone in mud	C.ft.	937		
2	Superstructure burnt brick in mud	,,	3,336		
3	Burnt brick in mortar	,,	873		
4	Burnt stone slabs 6" thick dressed and fixed ..	S.ft.	384		
5	Teakwood (Mysore) battened doors 1" thick shutters with hinges, bolts, padlocks, etc., complete	,,	182		
6	Teakwood battened windows with $\frac{3}{4}$" thick iron bars including hinges, bolts, etc., complete	,,	288		
7	Teakwood work wrought and put up with wood oiling	C.ft.	89·92		
8	Roofing with 1st Class Mangalore Pattern tiles on teakwood reapers with wood oiling, nails, etc., complete	Sqr.	32·34		
9	Ridge tiles set in mortar and pointed with cement	R.ft.	84		
10	Plastering with chunam	Sqr.	62·32		
11	White washing two coats	,,	62·32		
12	Chunam borders over roof	R.ft.	146		
13	Teakwood ornamental cave boards 9" long ..	,,	322		
14	Flooring with Cuddapah slabs on 3" concrete bed with cement pointing, etc., complete ..	Sqr.	19·43		
15	Chunam pointing to basement all round ..	,,	5·40		
16	Chocolate painting, 2 coats	,,	14·23		
17	Providing iron railings for portion in front room	R.ft.	58		
18	Tarring to woodwork doors and windows, etc.	L. S.	..		
19	Sundry and unforeseen charges such as clearing site and levelling ground	,,	..		

N. G. KRISHNA IYENGAR,
Executive Engineer.